



02/01/2023 – 02/28/2023

To Whom it may concern:

This material is currently produced at our "Independent Mine" (FDOT mine #11-490) and certified utilizing the "QC Certification System" as outlined in chapter 14 of the Aggregate Rule (14-103 F.A.C.). This material meets all current requirements of section 902 (Fine Aggregate 902-1 through 902-2.2) of the F.D.O.T Standard Specification for Road and Bridge Construction. Each load is certified by an individual ticket.

### 1001-FDOT Concrete Silica Sand Code F01

Procedure	Sieve/Test	Average	Unit	FLDOT Silica Sand
	#4 (4.75mm)	100	%	95-100
	#8 (2.36mm)	99	%	85-100
	#16 (1.18mm)	88	%	65-97
	#30 (.6mm)	58	%	25-70
	#50 (.3mm)	28	%	5-35
	#100 (.15mm)	2	%	0-7
	#200 (75µm)	0	%	0-4
AASHTO T-27	FM	2.24		2.05-2.45
AASHTO T-11	-#200 (75um)	0.21	%	
	Grad Loss	0.012	%	
AASHTO T-11	Wash Loss (#200/75um)	0.07	%	
AASHTO T-84	Absorption (Fine)	0.2	%	
AASHTO T-255	Total Moisture	3.1	%	
AASHTO T-21	Color	3		1-5
AASHTO T-84	SPGR Fine (Dry, Gsb)	2.638		
AASHTO T-84	SPGR Fine (SSD)	2.644		
AASHTO T-84	SPGR Fine (Apparent, Gsa)	2.653		

---

Sincerely,



## *Mario Cardenas*

Quality Control Manager

E.R. Jahna Ind, Inc.

Office: 352-394-7455

Cell: 863-557-0342

03/06/2023

Fax: 352-394-8730

**Name/Title**

David Clements / Mine manager