



02/01/2025

To Whom it may concern:

This material is currently produced at our Ortona Sand Company (FDOT mine #05-045) and certified utilizing the "QC Certification System" as outlined in chapter 14 of the Aggregate Rule (14-103 F.A.C.). This material meets all current requirements of section 902 (Fine Aggregate 902-1 through 902-2.2) of the F.D.O.T Standard Specification for Road and Bridge Construction. Each load is certified by an individual ticket.

1001-FDOT Concrete Silica Sand Code F01

| Procedure | Sieve/Test | Average | Unit | FDOT Concrete Silica Sand Code F01 |
|-----------|--------------|---------|------|------------------------------------|
| | #4 (4.75mm) | 100.0 | % | 95-100 |
| | #8 (2.36mm) | 99.8 | % | 85-100 |
| | #16 (1.18mm) | 94.4 | % | 65-97 |
| | #30 (.6mm) | 46.2 | % | 25-70 |
| | #50 (.3mm) | 11.7 | % | 5-35 |
| | #100 (.15mm) | 0.6 | % | 0-7 |
| | #200 (75µm) | 0.0 | % | |

Sincerely,

Mario Cardenas

Mario Cardenas
Quality Control Manager
E.R. Jahna Ind, Inc.
Office: 352-394-7455
Cell: 863-528-2335
Fax: 352-394-8730

Name/Title Mario Cardenas / Quality Control Manager